



Republic of the Philippines
University of the Philippines Cebu

Gorordo Ave., Lahug, Cebu City

(032) 233-3497 loc 102

<https://www.upcebu.edu.ph/>

bac_sec.upcebu@up.edu.ph

BIDS AND AWARDS COMMITTEE

SUPPLEMENTAL/BID BULLETIN

ADDENDUM NO. 2020-12-014

The following are additional items to consider in the **Repair and Replacement of Ceiling of Various Buildings**.

1. The new approved budget of the contract is **PHP1,294,000.00**.
2. The bid security shall be in the form of a Bid Securing Declaration, or any of the following forms and amounts:
 - a. The amount of not less than **Twenty-Five Thousand Eight Hundred Eighty Pesos (Php25,880.00)**, if bid security is in cash, cashier's/manager's check, bank draft/guarantee or irrevocable letter of credit; or
 - b. The amount of not less than **Sixty-Four Thousand Seven Hundred Pesos (Php64,700.00)** if bid security is in Surety Bond.

Section VI and VIII shall comprise the following

1. Removal of existing ceiling or ceiling boards of all identified areas, and disposal to designated area.
2. Supply and installation of the following:
 - a. Exterior Ceiling: Spandrel type ceiling 0.5mm thick with metal furring 0.5mm white

Area of Work	Area/Quantities	ABC
Library Canopy	~40 sq. m.	PHP 32,000
UPPS SRP Building	~500 sq. m.	600,000
Union Building	~140 sq. m.	292,000

- b. Interior Acoustic Ceiling: With 2x2x1/2 crossed T-runner metal framing

Area of Work	Area/Quantities	ABC
1F & 2F Union Building	~200 sq. m.	Included in the total ABC for Union Building
UGSD, AS, GH, Dorm	700 sheets 2x2x1/2 acoustic board 700 pcs metal crossed T-runners	147,000
ILC, CENVI	900 sheets 2x2x1/2 acoustic board 800 pcs metal crossed T-runners	223,000
TOTAL EXTERIOR AND INTERIOR CEILING WORKS		PHP 1,294,000.00

3. Reinstallation of affected ceiling lights.
4. For exterior ceiling, provide space/hole for passage of air at every column of the building (0.30x1.00m).
5. Replacement of FCB facia board with pre-painted plain sheet (Exterior Ceiling SRP).
6. Contractor to provide their own scaffolding for the project.
7. Contractor to ensure compliance to standard safety protocol.
8. PCAB License should be at least category C and D.
9. Contractor is required to conduct site visit and acquire site visit certification from CMO (Engr. Bascon).
10. For items where quantities are specified such must be delivered exactly.
11. For items where only the area of work is estimated, the winning bidder shall ensure that the actual area specified is considered notwithstanding the provided estimate.

For guidance and information of all concerned.

(sgd)

Lorel S. Dee, M.D.

BAC Chairperson